



वीरेन्द्रनगर नगरपालिका
नगर कार्यपालिकाको कार्यालय, सुर्खेत
कर्णाली प्रदेश, नेपाल



Bill of Quantity(BOQ)

योजनाको नाम: वडा कार्यालय भवन निर्माण
स्थान: वीरेन्द्रनगर-१६, सुर्खेत
स्वना नं:DP/BM/Works/02

Public Entity authorized signature: 

F.Y. 2079/080

| SN | Descriptions of work | unit | Quantity | Rate | | Amount | Remarks |
|------|---|------|----------|-----------|---------|--------|---------|
| | | | | In Figure | In Word | | |
| A | Civil Works | | | | | | |
| 1.00 | First class chimney brick masonry work in (1:4) cement sand mortar in G. F. | cum | 19.21 | | | | |
| 2.00 | Sal wood works for chankhats with all complete. | cum | 0.87 | | | | |
| 3.00 | Making and fixing of different size solid square rod grill with one coat primer works | kg | 377.49 | | | | |
| 4.00 | Collapsible shutter including manufacturing, welding, supply of material, painting and fixing | sqm | 4.35 | | | | |
| 5.00 | PCC(1:2:4) for RCC works . | Cum | 0.64 | | | | |
| 6.00 | Torssteel reinforcement bar for RCC work with cutting,bending,binding and laying with all complete. | kg | 124.24 | | | | |
| 6.00 | 38 x 75 mm thick sal wood frame with 3 mm thick fully glazed shutter fixing work with all complete. Size of shutter 1.829 x 1.22 =2.23 Sqm. | sqm | 11.50 | | | | |
| | Sub Total | | | | | | |
| | Vat | | | | | | |
| | Grand Total With Vat | | | | | | |

Form's Name:
Address
Email:
Telephone No.:

Name of Authorised Person:
Signature of Authorised Person:

Date: